

Vertical Solar System

2L1 Installation Unit | Modular Vertical Deployment



INSTALLATION UNIT	MODULES / UNIT	CAPACITY / UNIT	
2L1	2	1.19 kWp	1 pallet

KEY SPECIFICATIONS

PV Module	GStar GSD7S72T-595WT
Module Layout	2 modules, landscape
Module Size	2278 x 1134 x 30 mm
Orientation	Vertical
Rail	Steel
Posts	Steel
Hooks / Interfaces	Steel or aluminum
Reference Snow Load	3600 Pa - verify applicability
Reference Wind Load	2400 Pa - verify project basis
Structure Warranty	25 years

SYSTEM COMPONENTS

- PV modules with MagicFrame interface
- Steel rails
- Steel posts
- Hooks / connectors and accessories

IMPORTANT

Legacy Fence System parameters are used only where they remain applicable. Final dimensions for the current 595 W module configuration should be confirmed.